



NOTES:

1. EXISTING CONDITIONS INFORMATION PROVIDED BY SURVEY PERFORMED BY INBERG-MILLERS ENGINEERS IN JUNE 2012
 2. POST STRIPPING (4" DEPTH) EXISTING CONTOURS SHOWN AS DASHED LINES
 3. CONTRACTOR IS RESPONSIBLE TO FIELD VERIFY ALL UTILITY LOCATIONS PRIOR TO PERFORMING GRADING ACTIVITIES
 4. ALL GRADING IS TO BE PERFORMED IN ACCORDANCE WITH THE RECOMMENDATIONS MADE IN THE GEOTECHNICAL REPORT BY INBERG-MILLER DATED JULY 9, 2012
 5. GRADES REPRESENT APPROXIMATE BALANCED SITE CONDITIONS.
 6. ALL GRADES SHOWN ARE FINISHED GRADE, REFER TO PROJECT DETAILS FOR YARD/ROAD GRAVEL DEPTHS
 7. PROPOSED UTILITIES SHOWN SHADED BACK TO PREVENT VISUAL CONFLICT WITH FINAL GRADE CONTOUR LINES
 8. CULVERT SIZING AND DITCH LOCATIONS TO BE FINALIZED ON 95% SUBMITTAL WITH FINAL PLACEMENT AND LOCATIONS OF EQUIPMENT

EARTHWORKS QUANTITIES

Name	Cut(Cu. Yd.)	Fill(Cu. Yd.)	Net(Cu. Yd.)
FG_VOLUME	53070.42	55277.47	2207.08-<Fill>
BACKUP_VOLUME	2355.87	2509.16	153.29->Fill
TOTAL_FARTHWORKS	55426.29	57786.63	2360.37-<Fill>

*EARTHWORKS QUANTITIES SHOWN ABOVE DO NOT INCLUDE IMPORTED MATERIALS SUCH AS GRAVEL AND CONCRETE. IT IS ESTIMATED THAT APPROXIMATELY 9800 CY OF GRAVEL MATERIAL FOR SURFACING AND CONCRETE FOR BUILDING PADS WILL HAVE TO BE IMPORTED ONTO THE SITE TO ACHIEVE FINISH GRADES. QUANTITIES ALSO DO NOT INCLUDE SHRINK OR SWELL POTENTIAL.



Dig Safely.

AUC LLC

90% REVIEW SET
NOT FOR
CONSTRUCTION



1

<u>BOZEMAN OFFICE</u>	<u>CASPER OFFICE</u>
1800 West Koch, Suite 6	900 Werner Court, Suite
Bozeman, MT 59715	Casper, WY 82601
Tel: (406) 586-8364	Tel: (307) 265-0694
Fax: (406) 522-8460	Fax: (307) 265-2491
<u>GREAT FALLS OFFICE</u>	
200 Central St., Jr., 204	<u>BUTTE OFFICE</u>
Great Falls, MT 59401	

150

THIS BAR

PR
2

PROJECT NO
2012-250

1

ADD:
TBK

CHECKED
RR
GRAD
ENO CF

ED BY:
U
ING: I
REEK P

APPROVED
SLH
INDEX
PROJECT

1

PLOT D
10/2/2012

GRADING: INDEX ENO CREEK PROJECT

PREPARED FOR

AUC LLC
PREFI COUNTY WYOM

BELLE COUNTY, WYOMING